

# PROPOSAL

B COPA 6 - TEAR OFF - IN - LLBA

## BLUESTONE, INC.

P.O. Box 304  
NEW BOSTON, NEW HAMPSHIRE 03070  
(603) 487-5419  
(800) 639-4016 – Same phone # since 1984  
<http://bsprs.com>

Mr. Giao

PROPOSAL SUBMITTED TO Days Inn		PHONE 603-536-3520	DATE June 29, 2015
STREET 1513 US Route 3		JOB NAME NEW ROOF WITH 250 mil BLUESTONE COPA (Co Polymer Alloy) 6	
CITY, STATE and ZIP CODE Campton, NH 03223		JOB LOCATION US Route 3, Campton, NH - <b>Office area</b>	
ARCHITECT	DATE OF PLANS	LOOSE LAID AND BALLASTED	JOB PHONE

We hereby submit specifications and estimates for:

### 12,300 SQ. FT OF NEW ROOF WITH 250 mil BLUESTONE COPA 6

The old retired HVAC units will be removed. The old roofs will be removed and properly disposed of. The metal roof deck will be inspected for damage and repaired or replaced as needed.

Once the roof deck is repaired it will be covered with 2 layers of 1.5" ISOCYANURATE BOARD insulation. All joints will be staggered to eliminate thermal gaps. A temporary roof consisting of a **polyester** reinforced, BLUESTONE APP 2 base sheet will be installed. New STAINLESS STEEL drains will be installed.

Once the insulation and temporary roof are installed, 1 ply 250 mil BLUESTONE COPA (Co Polymer Alloy) 6 will be loose laid over the base sheet. Starting at the low point and working up with 8 inch **HEAT WELDED** side laps and 10 inch **HEAT WELDED** end laps. All joints will be staggered to maximize lap integrity and the strength of the roof.

Once the membrane is installed, new, flashing will be installed on all perimeters and the roof will be ballasted with the new stone at a rate of 10 lbs. per sq. ft.

TOTAL FOR 1 PLY 250 mil BLUESTONE COPA 6 FOR ONLY \$ 12.31 per sq. ft.== \$151,416.00  
OPTION FOR 2 PLY 320 mil BLUESTONE COPA 8 for only\$14.71 per sq. ft. == \$180,933.00

Roof deck repairs will be extra at \$65.00 per man hour plus materials.

*We Propose* hereby to furnish material and labor - complete in accordance with above specifications, for the sum of:

Payment to be made as follows:

50% down with progressive payments equal to the work completed

If material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado and other necessary insurance. Our workers are fully covered by Workman's Compensation Insurance.

Authorized Signature \_\_\_\_\_ Note: This proposal may be withdrawn by us if not accepted within \_\_\_\_\_ days

*Acceptance* – The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Signature:

Date of Acceptance

Signature:

Date of Acceptance