

PROPOSAL

B COPA 8 - TEAR OFF - IN - LLBA

BLUESTONE, INC.

P.O. Box 304
NEW BOSTON, NEW HAMPSHIRE 03070
(603) 487-5419
(800) 639-4016 - Same phone # since 1984
<http://bsprs.com>

Mr. Giao

PROPOSAL SUBMITTED TO Days Inn		PHONE 603-536-3520	DATE June 29, 2015
STREET 1513 US Route 3		JOB NAME NEW ROOF WITH 320 mil BLUESTONE COPA (Co Polymer Alloy) 8	
CITY, STATE and ZIP CODE Campton, NH 03223		JOB LOCATION US Route 3, Campton, NH - <u>Pool House roof</u>	
ARCHITECT	DATE OF PLANS	LOOSE LAID AND BALLASTED	JOB PHONE

We hereby submit specifications and estimates for:

6,360 SQ. FT OF NEW ROOF WITH 320 mil BLUESTONE COPA 8

The stone ballast will be removed and set aside. The 2 old roofs will be removed and properly disposed of. The metal roof deck will be inspected for damage and repaired or replaced as needed.

Once the roof deck is repaired it will be covered with 2 layers of 1.5" ISOCYANURATE BOARD insulation. All joints will be staggered to eliminate thermal gaps. A temporary roof consisting of a polyester reinforced, BLUESTONE APP 2 base sheet will be installed. New STAINLESS STEEL drains will be installed.

Once the insulation and temporary roof are installed, a 2 ply 320 mil BLUESTONE COPA (Co Polymer Alloy) 8 will be loose laid over the base sheet. Starting at the low point and working up with 4 inch HEAT WELDED side laps and 6 inch HEAT WELDED end laps. All joints will be staggered to maximize lap integrity and the strength of the roof. A 2nd ply of BLUESTONE COPA 4 will be fully adhered by HEAT WELDING to the 1st ply. All joints will be staggered with the 1st ply.

Once the membrane is installed, new, HEAVY DUTY ALUMINUM (.050) gravel stop will be installed on all perimeters and the roof will be ballasted with the original stone at a rate of 10 lbs. per sq. ft.

TOTAL WITH 2 PLY 320 mil BLUESTONE COPA 8 FOR ONLY \$ 7.47 per sq. ft. = \$65,106.00

Roof deck repairs will be extra at \$65.00 per man hour plus materials.

We Propose hereby to furnish material and labor - complete in accordance with above specifications, for the sum of: SIXTY FIVE THOUSAND ONE HUNDRED SIX AND 00/100

Payment to be made as follows:

50% down with progressive payments equal to the work completed

If material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado and other necessary insurance. Our workers are fully covered by Workman's Compensation Insurance.

Authorized Signature _____ Note: This proposal may be withdrawn by us if not accepted within _____ days

Acceptance - The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Signature:

Date of Acceptance

Signature:

Date of Acceptance